



NOTES:

1. CONTROL JOINTS SHALL BE PLACED PERPENDICULAR TO THE CURB AT FIVE FOOT INTERVALS.
2. FULL DEPTH EXPANSION JOINTS SHALL BE PLACED PERPENDICULAR TO THE CURB AT 20-FOOT INTERVALS.
3. MASTIC SHALL BE 3/8-INCH THICK MATERIAL AND BE PLACED FULL DEPTH.
4. SIDEWALK AND DRIVEWAYS SHALL BE BROOM FINISHED PERPENDICULAR TO THE CURB.
5. THERE SHALL BE MAINTAINED A MINIMUM OF FIVE FEET OF CLEARANCE FOR SIGNS, MAILBOXES, UTILITY POLES OR ANY OTHER STRUCTURES WITHIN THE SIDEWALK.
6. TWO INCHES OF MAINTENANCE ROCK OR CRUSHED SURFACING TOP COURSE IS REQUIRED UNDER ALL CONCRETE.
7. MINIMUM SIDEWALK THICKNESS:
 - 4 INCHES WHEN BEHIND TYPE 'A' CURB AND TYPE 'E' CURB
 - 6 INCHES WHEN BEHIND ROLLED CURB
 - 6 INCHES IN ALL DRIVEWAYS (TOP OF TAPER TO TOP OF TAPER)
8. ALL CONSTRUCTION AND MATERIALS SHALL MEET THE SPECIFICATIONS AND BE APPROVED BY THE CITY OF EPHRATA.
9. CITY STANDARD IS PLACEMENT OF SIDEWALK ADJACENT TO CURB. PLANTER STRIP MAY BE ALLOWED WHEN APPROVED BY THE CITY PUBLIC WORKS DIRECTOR.

TYPICAL CEMENT CONCRETE SIDEWALK	
EPHRATA PUBLIC WORKS DEPARTMENT	
CITY OF EPHRATA	
DRAWN _____ CHECK _____ SCALE NTS DATE 10/03/08	 WASHINGTON
A-2	

DATE	REVISION	BY